

CASE STUDY

Bhuku Family Farm — Operations Complex

Mazabuka, Southern Province

AGRICULTURAL	CIVIL WORKS	MAIN CONTRACTOR	SOUTHERN PROVINCE
4 + Fencing Structures + Perimeter	~9 Months Duration	ZMW 2.2M Confirmed to date	In Progress Status (2026)

PROJECT DETAILS

Client	Bhuku Family Farm
Location	Mazabuka, Southern Province, Zambia (approx. 150 km from Lusaka)
Scope	4 separate buildings across the complex, plus perimeter security fencing
Duration	Approx. 9 months
Bolide Role	Main Contractor — Design, Supply & Build
Contract Value	ZMW 2,200,000 confirmed to date; projected ZMW 2.4–2.5 million on completion (incl. perimeter fencing and interior finishes). Increase reflects price escalation.
Status	In progress — nearing completion (2026)

BACKGROUND

Bhuku Family Farm is an active commercial farm in Mazabuka, Southern Province. The farm required a comprehensive operations complex to support the storage, administration and logistics of a growing agricultural business. Bolide Infrastructure Solutions was engaged as the main contractor with responsibility for the full design, supply and build across the complex.

SCOPE OF WORK

- **Farm Storage Building:** General farm storage facility — structural frame, cladding, roofing and concrete floor slab.
- **Chemical Storage Unit:** Dedicated chemical storage building with appropriate ventilation and containment design.
- **Double-Storey Office Block:** Administrative office block across two floors — blockwork structure, reinforced concrete first floor slab, staircase, roof, plastering and interior finishes.
- **Vehicle & Implement Area:** Covered area for agricultural vehicles and equipment — steel-framed canopy structure.
- **Perimeter Security Fencing:** Diamond-mesh (chain-link) security fencing installed around the perimeter of the complex.

DELIVERY

The project is being managed from Mazabuka over a period of approximately nine months, with the Bolide team handling all site supervision, material procurement, subcontractor coordination and client reporting.

Site conditions presented the most significant challenge. The plot was not level, which required additional groundworks to establish stable, level foundations across the complex — including a greater volume of concrete, blockwork and laterite backfill than the original brief anticipated, with foundations taken deeper in places to reach suitable bearing. The double-storey office block was equally demanding from a technical standpoint, requiring careful sequencing of the reinforced concrete first floor slab before wall construction could continue on the upper level. Material price escalation over the construction period was reflected in a revised final contract value.

OUTCOME

This project represents Bolide's largest single civil works contract to date and demonstrates the capability to manage a multi-structure build as the main contractor — from initial design brief through to handover. The structures are at an advanced stage, with the remaining finishes underway and final handover to Bhuku Family Farm anticipated in 2026.

KEY PROJECT FACTS

Structures Delivered	4 (farm storage, chemical store, double-storey offices, vehicle area), plus perimeter fencing
Construction Type	Blockwork, reinforced concrete, structural steel framing, cladding and roofing
Location	Mazabuka, Southern Province (approx. 150 km from Lusaka)
Client Type	Private agricultural — direct client relationship
Contract Value	ZMW 2,200,000 confirmed to date; projected ZMW 2.4–2.5 million on completion (incl. fencing and interior finishes), reflecting price escalation
Duration	Approx. 9 months
Bolide Role	Main Contractor — Design, Supply & Build
Key Technical Works	RC first floor slab, staircase, double-storey blockwork, steel roof framing, steel canopy
Vehicle Canopy	Steel-framed canopy structure
Perimeter	Diamond-mesh security fencing around the complex
Status	In progress — completion anticipated 2026